



CAA/OT/EIA/0089/2019-2020

25th May, 2020

To: All Tenderers

**RE: REPLACEMENT OF AGL CABLES AND ACCESSORIES AT
ELDORET INTERNATIONAL AIRPORT
TENDER NO. CAA/OT/EIA/0089/2019-2020**

ADDENDUM NO. 6

The following are tender clarifications/addendum issued regarding the above tender in accordance to instructions to tenderers clause 7.1 of the bidding document for the referenced tender:-

ITEM NO.	ADDITIONAL CLARIFICATIONS / BIDDERS' QUESTIONS	REF. PAGE	RESPONSE
I.	A tenderer sought additional details about the manholes to be provided in this tender	Page 67 BoQ Item 4.4	All manholes covered in this item will have the following details: a) Internal Dimensions - As Provided in BoQ b) Manhole Cover - Reinforced Concrete slab, 200mm thick (to withstand 400KN force) with a 3mm thick Galvanized steel frame around it. c) Manhole Cover Reinforcement – D10 Double mesh at 100mm spacing. d) Concrete used – Class 30 e) Manhole Base – Reinforced concrete slab, 150mm thick f) Manhole Base reinforcement – D10 Double mesh at 100mm spacing g) Concrete to be used – Class 30 h) Manhole Walls – Double brick wall /Masonry minimum 300mm thick i) Internal finish - 10mm rendering class 20

2.	A tenderer sought clarification on Percentage of Retention applicable in this tender. In the Appendix to Form of Tender the Percentage of Retention is indicated as 10% of Interim Payment, while limit to retention it is indicated as 5% of contract sum).	Page 72 (clause 60.5)	Kindly note the Percentage of Retention shall be 5% of Interim Payment.
----	--	-----------------------	---

The closing/opening date remains as **28th May, 2020** at the same time and venue as per the tender document.

This addendum forms part of the bidding document and is binding on all bidders. All other conditions remain the same.



Patrick K. Wanjuki
GM (PROCUREMENT AND LOGISTICS)
For: MANAGING DIRECTOR/CEO